

Breakdown of Sewage Flow Estimation of WKCD (Upstream of existing sewer at Canton Road)

Sewage Master Plan Technical Notice No. 3

Population and Sewage Flow discharge to manhole FM4002142 at Canton Road (Ultimate Stage)

PVS No.	Street Block No.	Area (m ²)	Zoning	Total Residents	Total Hotel Guests	No. of Hospital Beds/Home for Age	Employees (Industrial)	Employees (Commercial)	Employees (Wholesale & Retail)	Employees (Restaurants & Hotels)	Employees (Community, Social Services, etc.)	Total Employees	Total Population	ADWF (l/d)
				R1 UFF (l/d)	-		J1 UFF (l/d)	J6 UFF (l/d)	J4 UFF (l/d)	J10 UFF (l/d)	J12 UFF (l/d)			
				190	0		630	80	280	1580	80			
54P	211018P	176341	GIC	0	1070	0	0	147	50	2176	588	2961	6992	3510880
58P	211010	6915	R(A)	2114	0	0	0	207	127	332	179	845	3804	992660
58P	211011	6595	R(A)	2017	0	0	0	397	100	450	128	1075	4167	1164230
58P	211017P	20169	R(A)	3185	0	0	0	211	584	410	230	1435	6055	1451750
59	211012	6467	R(A)	1673	0	0	0	602	44	33	229	908	3489	448810
59	211013	6037	R(A)	1562	212	0	0	507	90	57	106	760	3294	461080
59	211014	6406	R(A)	1657	0	0	0	563	223	36	169	991	3639	492710
Total												31440	8522120	

Note: The population information listed above is obtained from Appendix A of WK&TW SMP Review Report

98.636
(l/s)